



**FINANCIAL BID FOR ELECTRICAL WORK -PUNJAB GRAMIN BANK,
BRANCH - KANWAN, PATHANKOT**

S.N	Descriptions of items	QTY	Unit	Rate	Amount
1	LIGHT & FAN POINT (6 amp.)	30	No's		
	P & L 6 amp lights, fans, plug & five pin multi socket etc point wiring 2 x 1.0 sq mm + 1x1.5 sq mm PVC Insulated multi strand copper conductor cable ISI mark in conduit or under false ceiling with modular switches in Ms box complete in all respect with inter connection with button holder.				
2	16 AMP POINT	4	No's		
	P & L 16 amp. modular switch & five pin multi socket with indicator complete with interconnections between switch & socket with wiring 2 x 4 sq mm + 1x 2.5 Sq mm PVC insulated multi strand copper conductor cable form panel to point in P.V.C pipe with MS box recess in wall connected with 32 amp MCB in the panel. (1 Manager, 1 Panty & 1UPS).				
3	32 AMP WIRING FOR AC	4	No's		
	P & F 32 amp. wiring 2 x 4 Sq mm + 1 x 2.5 Sq mm from panel to point of AC, wire shall be multi strand insulated by copper conductor cable .Point shall have one AC starter in nearest switch board, connected with DP MCB in the panel and controlled by 4 way isolator in the panel. Wiring shall be in wall & under ceiling in PVC pipe.				
4.	PANEL TO UPS WIRING	15	Mtr.		
	2 x 6 sq mm PVC insulated multi strand copper conductor cable & 1.75 sq mm ISI mark form panel to UPS including PVC conduit pipe/ false ceiling complete in all respect				
5.	COMPUTER POINT (1 for each computer)	2	Nos.		
	Installation of computer points with 4 sockets and 1 switch with indicator including wiring with 2 x 1.5 mm + 1mm sq mm PVC insulated multi strand copper conductor cable in wall or under false ceiling with switches socket & box complete in all respect.				
6.	TELEPHONE POINT	1	Nos.		
	One Nos telephone jack, complete with interconnections Modular type ISI Mark including wiring with 2 x 0.51 sq mm copper with silver coated one pair PVC insulated sheathed twin core telephone wire (for telephone) from main line to telephone jack in Ms box Recess in wall or under computer.				
7.	CALL BELL : (Manager)	1	No.		
	P & F electrical point wiring for call bell with 2 X 1.5 sq mm PVC insulated multi strand copper conductor cable of in PVC conduit pipe wiring providing bell ceiling rose or connector & 6 amp ding done bell.				
8.	TUBE LIGHT-LED (On the walls)	1	No.		
	P & F 22 watts tube light one in the cashier cabin and in the back portion complete set. The tube lights should Philips/ Bajaj/ Company.(Strong Room)				
9.	WALL FAN	6	No		
	P & F of 16" wall fan with necessary wiring and switches.				
10.	CEILING LIGHT (36 watt LED)	11	No.		
	P & F of 2'x2' sq LED lights of Crompton co. The rate includes the complete fitting of chowks, rods and wire i.e. complete job in all respects.				
11.	UPS OUTPUT & INPUT	1	No's		
i)	Two DP 25 amp. Including box for input and output supply complete in all respect.				
ii)	8 way SPN distribution board double door with 6 nos MCB, 10 ka breaking capacity and 1 No 25 amp DP MCB ISI Mark (for UPS output				



	supply) in Ms cubical box of suitable size, necessary misc. hardware, knobs, rubber gas ket duly painted with low coats of red oxide one coat of enamel paint.				
iii)	P/F earth conducting with 8 nos copper wire earth pit to UPS panel.				
12.	DOWN LIGHT	10	nos		
	Providing & fixing 15 W LED recessed down lighter complete with all accessories in the ceiling including giving connections complete as required. Rate should include for all necessary supports for mounting the light fitting.				
13.	AC COPPER PIPE	30	rft.		
	Laying of AC copper pipe including cutting of walls and repair the same with the surface of walls. Copper pipe include 1/4" + 1/2 " & 3 core copper wire 2.5 sq.mm in 1/2" flexible pipe properly insulated complete in all respect. Copper pipe/ wire should not be more than 2'-0" in length near outer unit. Pipe should be of total line co.				
14.	AC DRAINAGE PIPE	30	rft.		
	Drainage pipe for AC 25 mm PVC pipe of supreme co. including fitting. Wall cutting and repair with cement mortar.				
15.	Providing CAT 6E Cable (Make D- Link) With Labor including 2 set of wires from Hub to Main Outdoor.	15	Meter		
TOTAL					
GST (18 %)					
GRAND TOTAL					
SAY					

AMOUNT IN WORDS :-