



**FINANCIAL BID FOR FURNISHING WORK
PUNJAB GRAMIN BANK, BRANCH - KANWAN, PATHANKOT**

S.N	Description of items	Qty	Unit	Rate (In Rs.)	Amount (In Rs.)
1.	MANAGER TABLE 5' X 2'-6" with side rack manager table -side rack of size 3'-3" X 1'-6" x2'-6" made of 19 mm thick anti termite commercial board/ Bishop Board. Top and vertical - exposed surfaces shall have 1mm. thick WHITE CEDAR laminate matching with existing table all exposed edges shall have teak wood molding duly polished. Lower portion 4" wide shall be in burgundy color laminate (Bank shade) on front and side. The rate also includes fitting of lockable keyboards, locks in drawers with Hettich ball bearing slides, terminals & C.P.U Shelf, foot rest of size 3" x 1.5". The non sun mica area should be duly painted or polished after making the smooth ground with second quality paint and chalk mittii i.e. Complete job in all respects.\	1	Nos.		
2.	MANAGER TABLE - TOP GLASS - 5'-0"X 2'-6"- 8MM with grinding of corners.	1	Nos.		
3.	ALUMINIUM PARTITION WALLS (Manager 5'-0" high) Manager Cabin partition wal and 1 partiton wall at back Manager Cabin of aluminum & glass partition. Lower 3'-6" high shall have pre - laminated board of Cedar white color. Uppar 1'-6" Portion shall have 8 mm thick glass. The Aluminum section should be 4 " x 1.75" x 2 mm ivory color powder coated	70	Sqft.		
4.	FLAP DOOR Flap door in two parts made of 19 mm thick ply with both side 1 mm thick laminate. Exposed edges shall have burgundy color T code molding. Rates imclude all fittings	28	Sqft.		
5.	BACK PARTITION (6'-0"X 5' -0") 19 mm thick ply with both side 1 mm thick laminate. Exposed edges shall have burgundy color T code molding. Rates include all fittings	30	Sqft.		
6.	FALSE CEILING (at 8'-6" high) P & F in position false ceiling of Armstrong 600 X 600 mm x 15 mm Dune Supreme RH 99 Prima file as specified by Armstrong Co. with suspenders wherever required making necessary cutouts for A.C. ducting. If any and necessary cutouts for diffusers and light fittings, taping and finished to proper line & level including making groves and trap doors for A.C. Unit in 18 mm thick M.R. Grade plywood with stainless steel hinges & locks with molding 1" x 1" for edges, if any including finishing with white plastic emulsion paint etc. complete in all respects. (Note: - Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, moldings, steps or any type of design etc.)	795	Sqft.		
7.	PANELLING PVC Paneling (Gold Di Heavy) Ivory & burgundy color with border As per Architect design	705	Sqft.		
	TOTAL				
	GST (18 %)				
	GRAND TOTAL				
	SAY				

AMOUNT IN WORDS :