

FINANCIAL BID FOR AC					
FOR PUNJAB GRAMIN BANK, HAIBOWAL KALAN DISTT. LUDHIANA					
S.N	Descriptions of items	Qty	Unit	Rate	Amount
1.	NEW AC SPLIT (1.5 TON)	3	Nos.		
	Supply and fixing new AC with stabilizer and stand complete in all respect.				
	GST (28%)				
	TOTAL (A)				
2.	AC COPPER PIPE	70	Rft.		
	Laying of AC copper pipe including cutting of walls and repair the same with the surface of walls. Copper pipe include 1/4" + 1/2 " & 3 core copper wire 2.5 sq.mm in 1/2" flexible pipe properly insulated complete in all respect. Copper pipe/ wire should not be more than 2'-0" in length near outer unit. Pipe should be of total line co.				
3.	AC DRAINAGE PIPE	70	Rft.		
	Drainage pipe for AC 25 mm PVC pipe of supreme co. including fitting. Wall cutting and repair with cement mortar.				
	TOTAL				
	GST (18%)				
	TOTAL (B)				
	GRAND TOTAL (A + B)				
	Stabilizer : Digital 100% copper 150 plus				

NOTE :-

- A. IN CASE DRAIN PIPE ARE LAID BY OWNER, CONTRACTOR SHALL NO BE PAID FOR THE SAME.
- B. PAYMENT OF THE COPAR PIPE FOR AC SHALL BE PAID 10' LESS, AS IT IS AVAILABLE WITH AC ON FREE OF COST.

TOTAL IN WORDS :